

**NATIONAL QUALITY INSPECTION AND SUPERVISION CENTER FOR
INDUSTRIAL CERAMICS OF BUILDING MATERIALS INDUSTRY**


INSPECTION REPORT

正本

No.:2021GW-0077

page 1 of 1

Client	Zibo Huao New Materials Co.,Ltd			
Manufacturer	/			
Size / Type	0-1mm		Brand	/
Sample state	Grain		Test Type	Contract
Reception Date/Place	2021.04.07;Center		Sample Amount	150g
No.	Test Items(Unit)	Test Result		Standard
		Individual	Average	
1	MgO(%)	0.0052;0.0052	0.0052	GB/T 3044-2020
2	Al ₂ O ₃ (%)	/	99.53	GB/T 3044-2020
3	K ₂ O(%)	0.0015;0.0015	0.0015	GB/T 3044-2020
4	Na ₂ O(%)	0.25;0.25	0.25	GB/T 3044-2020
5	CaO(%)	0.019;0.019	0.019	GB/T 3044-2020
6	Fe ₂ O ₃ (%)	0.0035;0.0035	0.0035	GB/T 3044-2020
7	SiO ₂ (%)	0.074;0.074	0.074	GB/T 3044-2020
The results only in charge of the detected samples.				
Remarks	/			



Authorization:

吴萍

Verification:

李晓明

Compilation:

0325

Seal

